

Proposed for extension and machine shade @Bari Barahmani,Jammu Tawi					
					INR
Sl. No	Description	QTY	Unit	Unit Rate	Amount
A	EARTHWORK/FILLING				
1	Filling available excavated earth (excluding rock) of floor. in layers not exceeding 50mm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 mm high. (Note :- After clearence from JCB floor levelling from client side scope.)				
		1158	Sft		
2	Concrete Interlocking Paver Blocks Application: Floor Tiles with sand and labour. (Note :- After clearence from JCB floor levelling from client side scope.)				
	Flooring	1158	Sft		
3	12mm cement plaster of mix ; 1:6(1cement :6 fine sand) including galvanized chicken wire mesh (24 gauge 12 mm size) to junctions of concrete and masonry work and other locations including cutting to required sizes, side laps of minimum 75 mm and fixing in position with galvanized iron wire nails, complete. (Cleaning of recycle planter from client.)				
	Recycle planter tank wall.	3215	Sft		
B	SHADE WORK FOR CRUSHER MACHINE ARRANGMENT				
1	Coloumn making with steel bars.cement,concrete,sand & shuttering.	6	Nos		
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor VI level in all shapes and sizes in ::Cement mortar 1:6 (1 cement : 6 coarse sand)	184	Sft		
3					
4	12mm cement plaster of mix ; 1:6(1cement :6 fine sand of zone-IV) including galvanized chicken wire mesh (24 gauge 12 mm size) to junctions of concrete and masonry work and other locations including cutting to required sizes, side laps of minimum 75 mm and fixing in position with galvanized	368	Sft		
5	Finishing walls with acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade .	368	Sft		
6	Mild steel work for making roof and coloumn.	1320	Kgs		
7	Supplying & Eraction of sheets of 0.50 mm TCT HI- RIB colour coated Galvalume 550 mpa steel for wall including all types of required accessories like screw, sub girt, flashing etc including loading,unloading & transportation.Wall Side Elevation	586	Sft		

8	ELECTRICAL WORK:- Providing and insatallation with complete work like conduiting,wiring,switch ,plate,gang box etc.as per required for supply of lights, Fan,Machine all	1.00	Job		
9	VEHICLE MOVMENT FLOORING WORK:- Concrete Interlocking Paver Blocks Application: Floor Tiles with sand and labour.(Note :- After clearence from JCB floor levelling from client side scope.)				
	Flooring	2200	Sft		
10	DRAIN LINE REPAIRE :- Repairing of drain line with civil work like cement and sand With complete provisioning of soil clening in route of drain line	40.00	RFT		
TOTAL (without tax/duty)					-
GST 18%					-
Total with GST					-
Price per SFT					-